Statement showing the probable quantities and rate of work to be executed for improving the Water-Supply to Kolar Town :—

No.	Details of work	Per	Quantity	Estimate rate Rs a. p.
	Constructing a semi-circular roughing filter in front of Ammarhalli Tank Sluice.—			
1	Roughing filter formed with rough stone packed with jelly ..	C. yd.	559	3 0 0
	Puddling the bed and sides of existing earthern reservoir.—			
2	Puddle work	,,	229	1 4 0
	Constructing sand filters.—			
3	Earthwork excavation, average soil up to soft rock	,,	1,937	0 8 0
4	Concrete in surki mortor	C. ft.	9,951	0 5 0
5	Burnt brick in surki mortor	,,	10,185	0 6 0
6	Burnt stone coping slabs, 3″ to 4½″ thick, two line dressed with edges champhered, etc., complete.	S. ft.	427	0 12 0
7	Burnt stone coping slabs 4½″ to 6″ thick, one line dressed on top with edges smooth, etc.	,,	457	0 6 6
8	1½″ Cadappa slabs covering over drains	Sqr.	9·57	30 0 0
9	Plastering with surki mortor	,,	124·21	6 0 0
10	Forming surki concrete drain	R. ft.	114	0 2 0
11	Small drain by the side of wall	,,	336	0 1 6
12	Colour washing	Sqr.	15·35	0 8 0
13	Forming cross drain by placing brick with open joints including covering.	Bricks 1,000	181·92	12 0 0
	Collecting, carting, stacking, etc., the filtering materials and using the same to filter beds.—			
14	Broken stones passing through 1½″ guage and retained on 1″ gauge.	C.yd.	193	2 8 0
15	Pebbles passing through ½″ gauge and retained on ¼″ gauge ..	,,	99	2 12 0
16	Course sand passing through a gauge with 10 meshes per inch retained on one with 20 per inch.	,,	100	2 8 0
17	Fine sand passing through a gauge with 20 meshes per inch and retained on one with 40.	C. yds.	316	5 0 0
18	Earth filling to extra space left between the concrete bed and the wall including consolidation.	,,	78	0 2 0
19	Making holes for fixing manhole frames and covers ..	No.	8	2 0 0
20	Teakwood ventilators with perforated sheets and expanded metal for pure water collecting cistern including masonry works, etc., complete.	,,	4	5 0 0
21	Forming bund alround filters	C, yds.	1,945	0 2 0
22	Constructing drain 1½′ X 2′ around the filter beds inside the bund to drain off the water.	R. ft.	400	0 12 0
23	Mild steel manhole cover with frame 2½″ X 2½″ as per type design.	No.	13	35 0 0
	Converting the existing settling tank and pure water tank into service Reservoir.—			
24	Constructing new valve cistern earthwork excavation ..	C. yds.	38	0 6 0
25	Concrete in surki mortor	C. ft.	78	0 5 0
26	Burnt brick in surki mortor	,,	557	0 6 0
27	Burnt stone slabs 4½″ X 6″ thick	S. ft.	110	0 6 0
28	Surki plastering	Sqrs.	5·33	6 0 0
29	Colour washing	,,	1·50	0 8 0
30	Mild steel manhole with cover 2½ X 2½′ complete including fixing..	Each	4	35 0 0
31	Making holes in the slab	,,	4	2 0 0
	Pipe laying for filters and service Reservoirs.—			
32	Laying and jointing 7″ pipe in 2½′ deep trench including lead or flange joints all the materials being supplied by contractor.	R. ft.	650	0 13 0
33	Laying and jointing 5″ do do ..	,,	275	0 11 0
34	Do 4″ do do ..	,,	275	0 9 6
35	Drilling holes in slabs 3 to 4½″ thick	No.	80	0 8 0
36	Earthwork excavation and refilling, for removing a 5″ cast iron pipe including removing joints and cleaning the pipes, etc., complete.	R. ft.	100	0 3 0
37	Constructing vavle cistren as per design	No.	13	38 0 0

H. F. MARKER,
Executive Engineer,
Spl. W. S. C. Division.

KRISHNARAJASAGARA WORKS.

Notification dated 1st November 1923.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Dam Construction Division, Krishnarajasagara, up to 15th December 1923, for the supply of fuel for the use of Krishnarajasagara Works on the North and South Banks from 1st January 1924 to end of 29th February 1924.

2. The approximate quantity required is 150 tons for each bank. But this is not guaranteed.

3. Tenders should be submitted in the form given below.

4. Each tender must be accompanied by a deposit of Rs. 100 as earnest money, and be superscribed "Tender for the supply of fuel to North and South Banks", in default of which, tenders will be rejected. The earnest money of the unsuccessful tenderers will be refunded.

5. The name of the successful competitor, whose tender will be accepted, will be posted on the Notice Board in the undersigned's office and also intimated to him in the usual course. No enquiries regarding the acceptance or rejection of tender will receive attention.

6. The rate tendered for each item should be for delivery at work site on either bank and separate tenders should be given for North and South Banks.

7. The supply is subject to the following specifications.

8. The supply should be made at the rate of 75 tons for each bank per month beginning from 1st January 1924 and completed before the 29th February 1924, without fail. In case of default, the contract will be cancelled, earnest money forfeited to Government, and other arrangements made for supply from elsewhere. The formal bond should also be signed and returned to this Office by the successful tenderer within a week of the settlement of tenders, failing which, the same penalty as stated above will be enforced.

N. SARABHOJA,
Executive Engineer,
Dam Construction Division.

FORM OF TENDER.

I hereby tender for the supply of fuel required in the Dam Construction Division, Krishnarajasagara Works, North and South Banks, from 1st January 1924 to end of 29th February 1924, *viz*, 150 tons for each bank, in accordance with the tender Notification dated 1st November 1923, and at the rates entered opposite to each item in the accompanying statement and in accordance with the sanctioned specifications and conditions. The quantity to be supplied monthly will be not less than 75 tons per month for each bank.

Contractor.

SPECIFICATION FOR FUEL-SUPPLY TO THE KRISHNARAJASAGARA DAM WORKS.

The fuel shall be of hard variety, such as, Jali, Thippajala, Devadari, Chigari, Tamarind, Hiddarse, Neralay, Jack, Margosa, etc., and wood of light variety, such as, Basari, Mango, Honge, etc., shall not be collected.

2. The wood shall be sawn into billets of 24 to 30 inches each in lengh and of 4½" to 9" in thickness.

3. These billets shall be carted to the stacking yard at the work site and in the space allotted built into rectangular stacks, each measuring 15' x 10' x 5' or 750 C.ft., being equivalent to 10 tons.

4. The stacks shall be built with sides vertical and top-level laying the billets evenly and closely at right angles to the direction of the sides and packing the interior closely with pieces laid regularly with lengths all in one direction.

5. Soft wood and wood of light variety shall be rejected and removed immediately by the contractor at his own cost.

6. The measurements of stacks so formed shall be taken a month later, thus allowing time for the fuel to dry. If the fuel stacks are not compact, suitable reduction should be made in their measurements for bills.

7. The rate for the supply shall be according to the tendered rate or the rate settled at the commencement of collection.

MEDICAL DEPARTMENT.

MATERNITY HOSPITAL, ROBERTSONPET, KOLAR GOLD FIELDS.

Abstract Notice dated 30th October 1923.

The undersigned invites the attention of the public to the page Nos. 684 to 686 of the *Mysore Gazette*, dated 4th October 1923, calling for tenders for the supply of diets, etc., and bedding and clothing to Maternity Hospital, Robertsonpet.

B. PERRITON,
Medical Officer.